

Corrigendum - 1

Date: 23.02.2024

Tender Ref No. III/SITC/UPS/2023-24

Tender Date: February 8, 2024

Re: Tender for Supply, Installation, Testing and Commissioning of Online UPS

Pg. No	Sr. No	Tender Particulars	Additional Information
Bati	tery Backup		
34	2.iii	(i) Sealed high rate discharge maintenance free valve regulated lead acid battery bank (VRLA) for 120 minutes back up time at 20 kVA Load - 2 banks.	Single unit backup in parallel operation should be 2 hours (120 minutes) on full load.
39	2.iii	(i) Sealed high rate discharge maintenance free valve regulated lead acid battery bank (VRLA) for 120 minutes back up time at 40 kVA Load - 2 banks.	
45	Annexure II (A) 6.4	Back up time - 120 minutes	
48	Annexure II (B) 6.4	Back up time - 120 minutes	
Exte	ended Warranty P	eriod	
8	Annexure I.10	Comprehensive AMC amount for 3 years on expiry of warranty period. 1st Year – 2nd Year – 3rd Year -	The bidder is required to quote for extended warranty period of 3 years and 5 years separately alongwith 3 years CAMC quote at points mentioned.
18	18.C	Annual Maintenance Contract (AMC) after expiry of warranty period:	
19	18.D	Maintenance	

1000

Contd. to Pg. 2



W

Pg. No	Sr. No	Tender Particulars	Additional Information
Isola	ation Transforme		
6	Annexure I.1	Supply, Installation, Testing & Commissioning of 20 kVA Online Parallel redundant UPS with SNMP facility and Isolation Transformer operating on 415V, 50Hz, 3 phase Input and Single phase Output with interconnecting suitable cable, Interconnecting 1 x 16 Sq.mm size copper cables or suitable cable between UPS and Switches & Batteries, UPS Body and Body Earth, as per actual site requirements.	The isolation transformer (whether external or in-built) should be with each single unit and not consolidate.
6	Annexure I.3	Supply, Installation, Testing & Commissioning of 40 kVA Online Parallel redundant UPS with SNMP facility and Isolation Transformer operating on 415V, 50Hz, 3 phase Input and 3 phase Output with interconnecting suitable cable, Interconnecting 1 x 16 Sq.mm size copper cables or suitable cable between UPS and Switches & Batteries, UPS Body and Body Earth, as per actual site requirements.	
Perf	ormance Bank Gu	larantee	
2	Point No. 4	Performance Security Deposit	The Performance Security Deposit means Performance Bank Guarantee to be submitted as per proposed proportion.
11	Point No. 5	CONTRACT EXECUTION	

--2--

Secretary (Estb.)